



Installation of API 610 Centrifugal Pumps to achieve a Flawless Start up for a Large Project



Presentation by:

Rob Vaughan &
Bill Robertson

Scotford Upgrader Expansion 1 (SUEx-1)

- Shell's Oil Sands Scotford Upgrader Expansion 1 Project installed 251 API 610 centrifugal pumps. The plant was successfully started up in the spring of 2011. Shell has developed a worldwide quality program aimed at delivering a Flawless Start-up. This presentation focuses on the installation of these API 610 centrifugal pumps. Topics from each phase of the project will be discussed from initial design, specification, inspection, installation, preservation, and commissioning & start-up.



Scotford Upgrader Expansion 1 (SUEX-1)

Introduction to Project & Pump Scope

- 21 orders for 251 pumps from 1 vendor
- Ranging from 10-3000KW all API610 design
- 8 manufacturing sites worldwide
- \$100M total for purchase order
- 4 Area Works Construction Contractors
- 5 process units for a 100 BBPD Heavy Oil Upgrading Facility
- Engineering and procurement done from 5 locations worldwide with 17 EPC Design Engineers working on rotating equipment with oversight from 3 Shell rotating equipment personnel
- Prime construction contractor was a joint Shell and Bechtel owners team.



HMU

TIC

ROTATING EQUIPMENT	
COMPRESSORS / FANS / BLOWERS	7
AIR COOLER FANS	34
PUMPS	42

SPECIAL EQUIPMENT	
FANS COMMON LUBE OIL SKID	1



SRC


ROTATING EQUIPMENT

COMPRESSORS / FANS / BLOWERS	7
AIR COOLER FANS	34
PUMPS	42

SPECIAL EQUIPMENT

LUBE OIL SKIDS	8
PUMPS	1
COMBUSTION AIR BLOWER	1
PUMPS CENTRAL SEAL FLUSH PLAN 54 SKID	1

KBR



A&V

ROTATING EQUIPMENT	
COMPRESSORS / FANS / BLOWERS	4
AIR COOLER FANS	46
PUMPS	46

SPECIAL EQUIPMENT	
LUBE OIL SKIDS	8
CENTRAL SEAL FLUSH PLAN 54	1

KBR



RHC

PCL

ROTATING EQUIPMENT	
COMPRESSORS / FANS / BLOWERS	12
AIR COOLER FANS	52
PUMPS	58

SPECIAL EQUIPMENT	
LUBE OIL SKIDS	1
HYDROGEN MAKE UP / RECYCLE PUMPS	1

PUMPS LOCAL SEAL FLUSH PLAN 54 SKIDS
HYDROGEN MAKE UP/RECYCLE TEMPERED WATER SKID
LCF SEAL OIL INJECTION SKIDS



BANTREL

U&O

ROTATING EQUIPMENT	
FANS / BLOWERS	5
PUMPS	94

TOP ENTRY MIXERS	4
SIDE ENTRY MIXERS	2

STEAM TURBINE DRIVERS	7
ELECTRIC GENERATORS	7
INSTRUM AIR COMPRESSORS	2

SPECIAL EQUIPMENT	
LUBE OIL SKIDS	1
STEAM TURBINE-GENERATOR PUMPS	1

Rotating Equipment Path to Start-up

■ Design

1. Review Lessons Learned from previous Shell projects and incorporate into Purchasing Documentation & Technical Specifications
2. Specification selection leading to clarification rounds with vendors to ensure alignment on expectations
3. Key Learning's from Design Phase

■ Procurement

4. Identify ITP and Quality Surveillance Strategy
 - 3rd Party Inspection vs. Client Inspection
5. Key Learning's from Procurement Phase

■ Construction

6. Rotating Equipment Construction Organization
7. Engineering Receipt Inspection Program & Non Conformance Record Generation
8. API 686 Installation & Shell's Minimum Requirements for Rotating Equipment
9. Inspection and Test Plan
10. Construction Installation Issues
11. Key Learning's from Construction Phase


■ Start-up

12. Mechanical Completion
13. Pre-Start-up Issues
14. Start-up Issues and Outcome

Shell's Quality Program Flawless Project Delivery



- Shell has a formal World Wide Quality Program aimed at delivering a Flawless Start-up



Design: LL and Specification Selection

Shell's Quality Program Flawless Project Delivery



- Lessons learned (LL) and Practices Worth Repeating (PWR) were reviewed and carried forward from previous projects. It is important to capture both positive and negative experiences from a variety of sources (previous project mgmt, maintenance, operations, industry colleagues, etc)
- Our LL list went through many review cycles producing quality input being placed in the contractual language of the purchase order. (Sources of contractual language include ITP's, audit plan, technical specifications, technical notes, drawings, etc)
- Specification selection leading to clarification rounds with vendor is a process that can not be rushed and needs to take multiple rounds. All relevant LL and PWR were reviewed with vendor

Machinery Learnings From AOSD – Upgrader and Scotmods
 Compiled by Rob Vaughan
 Updated: Aug 20, 2009

	Learning/Comment	Source	Proposed Action for AOSPE	DISPOSITION	Status
1	Centrifugal Pumps DEP 31.29.02.30-SCAN				
1.1	P-22201A,B, P22301 Multiple Failures	RCA team	Incorporate RCA recommendations into Centrifugal Pump DEP 31.29.02.30-SCAN where possible		DEP complete FED 3 design not complete. Added 3x50% pumps on FED
1.1.1	1. Erosion	RHC-SCTU03-00103/040065/04/0134	Consider using 410 S/S and 3x50% pumps during FED 3 design.		1. Complete
1.1.2	2. Inner case bonding		1. Erosion – Consider using a diffuser pump with a stiff shaft in this service. Eliminate impeller wear rings. DEP 31.29.02.30-SCAN, Section 3 has these requirements.		2. Complete
1.1.3	3. Warm-up issues		2. Inner case bonding – Don't use 316 S/S on a multistage pump above 500 deg C. DEP 31.29.02.30-SCAN Appendix 1 table 1-1		3. Complete
1.1.4	4. Thrust bearing failures		3. Warm-up issues – Consider automated warm-up system for this service. FED 3 design.		4. Complete
1.1.5	5. Fire on insulation		4. Thrust bearing failures – FED 3 design		5. Complete
1.1.6	6. Inadequate insulation		5. Fire on insulation – FED 3 design		6. Complete
1.1.7	7. Warm-up from bottom a all hot pumps		6. Inadequate insulation – FED 3 design		
1.1.8	8. Circulation warm-up line c/w pump will save 10 m3/hr of HGO		7. Warm-up from bottom casing drain – DEP 31.38.01.11 para 4.2.2.5		
1.1.9	9. Cut elbow on warm-up line – use long radius in particulate service		8. See 3 above.		
			9. FED 3 design		7. Complete
1.2	P-22201A,B, P22301 Seal failures – seal axial growth inadequate	Jarrett	Review hot pump seal design during warm-up in design phase. Consider alternative seal design.		
1.3	RHC charge pump spillback lines too small – need more flow	High Priority list	Review during FED 3 on a per pump basis. This is not necessary on all pumps.		
1.4	P21106 and many other examples of inadequate min flow at startup and normal running	High Priority list	Added a paragraph stating that all spillback lines in black oil service needs to be min schedule. DEP 31.38.01.11 para 4.2.2.1.7		Complete
1.5	RHC P22201B spillback line rupture	High Priority list	Review seal design for hot pumps. Consider alternative seal design. Consider use of seal flush flow add to seal. DEP 31.38.01.11 para 4.2.2.1.7		
1.6	P-22401C seal fire	High Priority list	DEP 31.29.02.30 para 5.4.2.1 states that top up is required for pumps above 200C thermal growth issues. Leave DEP as is.		Complete
1.6	Top/top pumps increase maintenance time, increase platforms, increase safety hazards, and increase warm-up issues	High Priority list			

Design: LL and Specification Selection

Lessons Learned Example:

LCF Charge Pump

- Experienced Erosion issues led to diminished performance and poor life of thrust bearing
- Leaks occurred at the head gasket due to differential expansion in the casing during the warm up of the pump, especially in the winter time
- This was reviewed with the vendor and led to design a centrifugal, between bearing, 9 stage, radially split, double casing BB5 pump including a:
 - Oversized balance drum with solid tungsten carbide bushing
 - Carbon steel barrel with Stainless Steel Overlay
 - Addition of 4 temperature indicators, top / bottom, inboard and out board of the casing to help operator to warm up pump evenly
 - External balance line with Ultra sonic flow meters
 - Tungsten Carbide direct laser deposit on impellers and sleeves
- String Test of Prototype LCF Charge Pump revealed issues with rotor dynamics with balance drum and vibration issues with skid and motors



Key Learning's from Design Phase

- To do a proper and complete Lessons Learned Review takes a lot of time! **{PLAN AHEAD}**
- Incorporating these learning's into the contractual language of the Purchasing Documents is Critical to being able to get what you need.
- Specification clarification / review meetings with vendor can not be rushed and need to be documented to ensure alignment on expectations.
- Our Project experienced too many late changes to purchasing documents resulting in escalating costs and projected schedule delays due to confusion of specifications requiring more clarifications.
- There were too many drawing inconsistencies with fabricated equipment. Issues found after fabrication had begun, due to coinciding events of concurrent fabrication and engineering.
- Developed an effective process with vendors and EPC to keep track of all new relevant issues to track them to closures. Rolling Action Item List (RAIL) worked well.



Identify ITP Requirements & Quality Surveillance Strategy

- Having detailed clear Inspection and Test Plans is very important as this provides a leading indicator of the quality of the equipment you will be receiving
- Debate between 3rd party contract inspectors being used for inspections vs. client personnel (maintenance, operations, project resources) for inspections
- SUEX-1 used a combination of 3rd Party contract inspectors and dedicated client personnel inspection. We had dedicated client personnel providing full time inspection at vendor shops during fabrication of critical equipment orders
- Schedule many multidisciplinary visits to package equipment vendors to ensure that all disciplines get adequate representation during inspection



Key Learning's from Procurement

- 3rd Party Inspection was an expensive program that produced ultimately poor results with regards to pre-inspected equipment being sent to site with obvious poor quality.
- Need to have better alignment on expectations and alignment with 3rd party contract inspector to ensure goals are clear. Remind them they are to report all findings and they work for the Client not the Fabricator.
- Do not let Procurement / Expediting drive the quality out of vendor shop. If necessary keep equipment at vendor's shop as long as possible to provide time to correct known deficiencies. Transferring scope or known rework to site is not a good idea as it will push out your schedule and drive up your costs.
- Use more client personnel for critical equipment inspection, { Example BB5 Charge Pumps} especially for prior to shipment inspection. Best results are to have the receipt inspection done at the vendor shop prior to shipping of equipment.
- For Packaged Equipment use multi-disciplinary client inspection teams. Our results indicated that rotating equipment vendors are being asked to package and their competence or experience is not high within the other disciplines, etc (tubing, piping, heat trace, wiring, CSA, CRN & ABSA issues...etc)



Construction Program Outline

- Construction Organization Alignment
- Engineering Receiving Inspection Program {Top Findings, upon receipt of equipment}
- Installation Procedures {API 686 Installation & Shell's Minimum Requirements for Rotating Equipment Installation}
- Field Construction Inspection Test Plans

- Construction Issues
 - Cleanliness & Preservation {Pre and Post Installation}
 - Levelling & Soft Foot
 - Grouting
 - Field Machining
 - Piping Installation

- Alignment
- Construction Key Learning's



Construction Organization

- Daily meetings with Operations, Vendor Field Representative, Shell Millwrights & Project Engineering staff for inspection assignments and overall alignment
- Formal weekly meetings with Area Works Construction Contractor. These meetings have Rolling Action Item Lists and allow the AWC to have clear communication lines to the project for immediate issue resolution
- AWC has direct access and works continually with Shell Inspection on a daily basis
- Rotating Equipment Installation Workshops once a month, site meetings to review installation procedure at various stages of project. Key aspects of upcoming jobs

Benefits of this Construction Organization

Resulted in Success

- Clear open lines of communication between field and engineering across all companies e.g. (Construction Contractor, Projects & Operations)
- Timely issue resolution
- Management aware of team progress and sometimes included into meetings



Engineering Inspection Receipt Program & NCR Generation

- EIR Program consisted of all Equipment to receive inspection upon arrival to site by Shell Operations and Maintenance Staff.
 - For the Rotating Equipment the team consisted of 8 millwrights, 2 contract inspectors, and 3 engineers dedicated to program
 - All equipment received inspection according to premade checklists & all deficiencies were photographed and recoded for NCR records (*used API 686 Ch 3 as guide for checklist development*)
- For 251 pumps a total of 1062 ERRORS FOUND CAUSING 313 NCR'S TO BE WRITTEN!**
- Typical Deficiencies Discovered during EIR Inspections



Engineering Receipt Inspection Check lists

25183-110-GOR-M02-00003, Rev. 1
Inspection Test Record (ITR) – Engineering Inspection Request (EIR)

INSPECTION TEST RECORD (ITR) ENGINEERING INSPECTION REQUEST (EIR)			
PROJECT NAME		PROJECT NUMBER	
EIR NUMBER		P.O. NUMBER	
REQUEST DATE		MATERIAL RECEIPT DATE	
INSPECTION DATE		MRR NUMBER	
DESCRIPTION OF MATERIAL TO BE INSPECTED			
ENGINEERING DISPOSITION (CHECK AS APPLICABLE)			
ACCEPT AS IS	<input type="checkbox"/> NO (IF "NO" COMPLETE THE FOLLOWING UOS&D CONDITION AND DISPOSITION) <input type="checkbox"/> YES		
UOS&D CONDITION			
UOS&D DISPOSITION			
SPECIAL STORAGE REQUIRED	<input type="checkbox"/> NO <input type="checkbox"/> YES (IF "YES" COMPLETE REQUIREMENTS SECTION)		
REQUIREMENTS			
SIGNATURES			
RESPONSIBLE FIELD ENGINEER	PRINT		DATE
	SIGN		
WAREHOUSE SUPERVISOR	PRINT		DATE
	SIGN		

	ENGINEERING INSPECTION REQUEST CHECKLIST ROTATING EQUIPMENT
---	--

Item	Yes	NA
1		
2		
3		
4		
5		
6		
7		
8		
9		
10		
11		
12		
13		
14		
15		
16		
17		
18		
19		
20		
21		
22		
23		
24		
25		
26		
27		
28		

Typical EIR Program Deficiency Findings From Several Shell Projects





- **Why is an EIR Program Necessary:**
- To find missed items from factory inspection, it is critical to catch prior to installation
{Last chance to verify, to get it right}
- For Documentation Reasons, you need accurate records (photographs of every issue works best)
- Capture the LL for the next project and pass along the findings to improve the quality of the equipment coming from our future vendors

- **When to perform an EIR inspection:**
- ASAP... at PM warehouse
- Important to take equipment out of packing and inspect it; then start preservation program.
- Do not want the Construction Contractor to have to deal with late known problems that should have been found at either the pre-shipment inspection or during an EIR.
- EIR findings that require action are very expensive and distracting to a construction contractor's schedule.

Construction Issues

Typical EIR Program Deficiency Findings From Several Shell Projects




Typical issues:

- 1. Damage due to shipping
- 2. Verify ship loose items (misplaced, lost in transit, never shipped, etc...)
- 3. Shims not laser cut and/or are the wrong size
- 4. Motor does not have 8 jacking bolts
- 5. Suction/discharge/drain flanges are not covered with a metal closure
- 6. Water present in the case and drain lines
- 7. Oil mist lubricated bearings preserved with grease
- 8. Mounting pads do not meet the level requirements of API 610 and Purchase Order
- 9. Baseplate lacks levelling screws
- 10. Motor is bolt bound



Installation Procedures

- Installation Procedure {API 686 & Shell's Minimum Requirements for Rotating Equipment Installation}
- Need to be reviewed and signed off by Constructor, and Shell
- Important to obtain input from Operations & Project staff as well as, for AWC buy in



SCOTFORD UPGRADER EXPANSION 1 PROJECT

PROCEDURE NO: 25183-110-GPP-GCEM-00005, Rev. 0, 2008-09-10

PROJECT CONSTRUCTION PROCEDURE MINIMUM REQUIREMENTS FOR ROTATING EQUIPMENT INSTALLATION

Discipline Team Lead Rotating Bill Robertson	Mechanical Rotating Resident Engineer Donny Issa	Manager, Field Engineering Cameron Gerdes	Shell Manager, Quality Mark Looijer

0	2008-09-10	ISSUED FOR USE	B. Robertson	D. Issa	C. Gerdes
NO	DATE	REVISION	BY	CHKD	APPR
SHELL CANADA LIMITED SCOTFORD UPGRADER EXPANSION 1 PROJECT PROJECT CONSTRUCTION PROCEDURE MINIMUM REQUIREMENTS FOR ROTATING EQUIPMENT INSTALLATION				25183-110-GPP-GCEM-00005	REV 0

Security Level 2
 Electronic documents, once printed, are uncontrolled and may become outdated.
 Refer to electronic documents in IntraWorks for current revisions.

Bechtel Confidential
 © Copyright Bechtel Corporation 2005. Contains confidential and/or proprietary information to Bechtel and its affiliated companies which shall not be used, disclosed or reproduced in any format by any non-Bechtel party without Bechtel's prior written permission. All rights reserved.

Inspection and Test Plan

Key Points ITP's

- Important to provide list of key surveillance, review, witness and hold points to construction contractor for ITP development
- Need clear expectations on ITP steps as the ITP is contractual language
- For SUEX-1 the Major Hold and Witness Points for the Field Inspection and Test Plan for Centrifugal Horizontal Pumps were:

- Hold:

- Submit Contractor Installation Work Packages (first of every kind)
- Pre-grouting Meeting for alignment of path forward
- Oil System Installation, verification and flushed
- Final Alignment

- Witness:

- Pre-installation Baseplate level check
- Pre-installation Preliminary alignment
- Pre-installation soft foot check
- Soft foot check
- Piping equipment / suction system cleanliness
- Pipe stress and flange alignment

Hold

Witness



Inspection and Test Plan

Field Inspection and Test Plan of Centrifugal Horizontal Pumps

INSPECTION TEST PLAN		25183-119-GGR-MP1-00002, Rev. 9					
DATE SUBMITTED		2008-04-23					
WORK LOCATION AREA		COMMON					
ITP DESCRIPTION		Field Installation of Centrifugal Horizontal Pumps					
TASK #	TASK DESCRIPTION	TECHNICAL REQUIREMENTS (See Note 1 Below)	O F F S I T T E W O R K K	VERIFYING DOCUMENTS: ITR's (See Note 2 Below)	CONTRACTOR	BECHTEL/SHELL	THIRD PARTY INSPECTOR
1	2	3	4	5	6	7	8
A Verification Prior to Installation							
A.1	Material receiving		N	Y	25183-119-GGR-MP1-00002 Inspection Test Record (ITR) - Un satisfactory Deliv. Sheet, and Damage Material Form (UDMADMG)	W	S
A.2	Verify name plate data is correct	Equipment Data Sheet	N	Y	25183-119-GGR-MP1-00002 Inspection Test Record (ITR) - Centrifugal Horizontal Pumps Installation Checklist (M1E)	I	S
A.3	Verify equipment preservation	Preservation Procedure (Vendor) 25183-119-GPP-GCE-00027 Construction Procedure (CP) - Preventive Maintenance* 25183-119-GPP-GCEM-00003 Construction Procedure (CP) - Rotating Equipment Storage and Preservation*	N	Y	Preventive Maintenance Card	I	S
A.4	Submittal installation procedure	Installation Manual (Vendor) API 688 Recommended Practices for Machinery Installation & Installation Design ESTD 11-3-21 Rotating Equipment - Installation, Check-out & Testing 25183-119-GPP-GCEM-00002 Construction Procedure (CP) - Minimum Requirements for Rotating Equipment Installation* 400 1418 080 055 901 Chevron Concrete - Standards General Notes	N	Y	Installation Procedure / Work Package (Contractor)	I	NS
A.5	Verify equipment subcomponents ASMA inspection requirements (where applicable) are completed	25183-119-GPP-GCE-00009 Construction Procedure (CP) - Certifying Pressure Equipment and Piping Systems in Alberta* 25183-119-GPP-GCEM-00001 Construction Procedure (CP) - Coordinating Inspectors of Pressure Equipment with ASMA*	N	Y	ASMA Certificate of Inspector "A" Number	I	R
A.6	Verify foundation release		N	Y	25183-163-GGR-EB2-00002 Inspection and Test Record (ITR) - Concrete Pour Card (C02)	H	S
A.7	Verify anchor bolt projections	API 688 Chapter 4 Para 2.10.8 400 1418 080 055 901 Chevron Concrete - Standards General Notes	N	Y	25183-163-GGR-EB2-00002 Inspection and Test Record (ITR) - Concrete Pour Card (C02)	I	S
A.8	Verify anchor bolt location	General Arrangement Drawing (Vendor) API 688 Chapter 5 Para 3.5.4 Foundation Drawing	N	Y	25183-163-GGR-EB2-00002 Inspection and Test Record (ITR) - Concrete Pour Card (C02)	I	S

Preservation & Cleanliness

{Pre and Post Installation}



**SCOTFORD UPGRADER EXPANSION 1 PROJECT
PROJECT CONSTRUCTION PROCEDURE
STORAGE AND PREVENTATIVE MAINTENANCE**



25183-110-GPP-GCEM-00002, Rev. 0, 2008-06-19

Prepared by: Tina Yeung

Approved by: Cameron Gerdes

SCOTFORD UPGRADER EXPANSION 1 PROJECT

PROCEDURE NO: 25183-110-GPP-GCEM-00002, Rev. 0, 2008-06-19

**PROJECT CONSTRUCTION PROCEDURE
STORAGE AND PREVENTATIVE MAINTENANCE**

Manager, Contracts <i>[Signature]</i> Ned Burrows	Manager, Construction <i>[Signature]</i> Tom Eggleston	Director, Construction <i>[Signature]</i> Carl Lake	Manager, Resident Engineering <i>[Signature]</i> Alan Jahns
Manager, Field Engineering <i>[Signature]</i> Cameron Gerdes	Manager, Quality Assurance <i>[Signature]</i> Richard Valdez	Shell Manager, Quality <i>[Signature]</i> Mark Looijer	Shell Manager, Construction <i>[Signature]</i> Fred Hodges
Manager, Procurement <i>[Signature]</i> Hugh Deighton			

			<i>[Signature]</i>	<i>[Signature]</i>	<i>[Signature]</i>
0	2008-06-19	ISSUED FOR USE	T. Yeung	D. Karpiak	C. Gerdes
NO	DATE	REVISION	BY	CHKD	APPR
	SHELL CANADA LIMITED SCOTFORD UPGRADER EXPANSION 1 PROJECT PROJECT CONSTRUCTION PROCEDURE STORAGE AND PREVENTATIVE MAINTENANCE			25183-110-GPP-GCEM-00002	REV 0


Security Level 2
Electronic documents, once printed, are uncontrolled and may become outdated.
Refer to electronic documents in InfoWorks for current revisions.

Bechtel Confidential
© Copyright Bechtel Corporation 2005. Contains confidential and/or proprietary information to Bechtel and its affiliated companies which shall not be used, disclosed or reproduced in any format by any non-Bechtel party without Bechtel's prior written permission. All rights reserved.

Construction Issues

Preservation {Pre Installation}

- Important to have constant surveillance as conditions on a construction site change daily with work activities, weather, etc.
- Heated indoor storage and constant auditing are best preservation program (*API 686 Ch 3 par 1.5.1-1.5.19*)
- Assign ownership of program early {our experience went through 2 preventative maintenance companies during project}
- Define on an equipment tag basis what equipment needs what type of PM; have PM Cards and an overall database; follow up with regular inspection.



**Shell VSI 68
Mineral Oil**



HEAVY DUTY RUST GUARD



**CHEVRON SRI GREASE
NLGI 2**



**DARINA[®] XL
PREMIUM MULTIPURPOSE GREASES
FOR TOUGH, LASTING PROTECTION**



Construction Issues

Preservation

{Post Installation}

Issues

- Hoarding damaged / removed exposing equipment to weather
- Water in Lube Oil skids
- Short / modified dip sticks
- Gear boxes with no oil
- Uncovered flanges
- Tubing and insulation damage
- Incomplete PM cards
- Key to audit regularly and express importance to construction contractor



**Shell VSI 68
Mineral Oil**



HEAVY DUTY RUST GUARD



**CHEVRON SRI GREASE
NLGI 2**




**DARINA[®] XL
PREMIUM MULTIPURPOSE GREASES
FOR TOUGH, LASTING PROTECTION**



Leveling & Soft Foot

- Room for levels on pump pedestal so pump does not have to be removed to mount level
- Ensure motor is not bolt bound; this is critical for alignment
- API 686 tolerance of 0.002" per foot is a very tight (API 686 Ch 5 3.9.4.4 leveling & Ch 7, paragraph 5.4.4.1 soft foot)
- Level can only be achieved after a constant temperature of the steel, concrete and air is normalized {anticipate 24-36 hrs of constant temperature}
- Test & calibrate levels regularly. Use multiple levels to ensure accuracy {these things get dropped, damaged and uncalibrated very easily}



Construction Issues

Leveling & Soft Foot




Follow Procedure


Test if pump or pedestal is not level

(API 686 Ch 5 Appendix D Figures D1-D10)

Need Pre Grout NCR Agreement Sign off by vendor

“YOU GROUT IT YOU OWN IT”





- Desire to achieve Concrete Surface Profile 9
- Chipping (not bush hammering) to remove top laitance layer and expose cracked aggregate (*API 686 Ch 5 par 3.6.2*)
- Preparation of bottom of base plate (buff/clean)
- Ensure area is clean (no oil, water, dust, rags)



Construction





Sikadur® 42 Grout Pak LE^{CA}
Pre-Propportioned, Epoxy Base-Plate, Grouting System

Product Data Sheet
Edition 04 2007
CSC Master Format™ 03 63 00
Sikadur® 42 Grout Pak LE^{CA}

Description	SIKADUR® 42 Grout Pak LE ^{CA} is a high strength, multi purpose, three-component, low exotherm, low dusting, solvent-free, moisture-insensitive, epoxy grouting system to cast base-plates.
Where to Use	<ul style="list-style-type: none"> ■ Precision setting of baseplates. ■ Grouting under equipment, including heavy impact and vibratory machinery, reciprocating engines, compressors, pumps, presses, etc. ■ Grouting under crane rails.
Advantages	<ul style="list-style-type: none"> ■ Meets API Standard 686. ■ Low peak exotherm. ■ Low dusting, ready-to-mix, pre-proportioned kits. ■ Moisture insensitive. ■ Non-stains. ■ Corrosion and impact resistant. ■ Stress and chemical resistant. ■ High compressive, tensile and shear strengths. ■ High vibration resistance. ■ Low coefficient of thermal expansion; compatible with concrete. ■ Material does not require heated transportation.
Technical Data	
Packaging Volumes	
Component A	16.28 kg (36.0 lb)
Component B	3.42 kg (7.5 lb)
Component C	6.4 kg (14.1 lb) (62.7 kg bags)
Yield (per kg)	58.6 L (20 ft ³)
Colour	Concrete Grey
Shelf Life	2 years in original, unopened packaging. Slow dry at 5° - 30°C (41° - 86°F). Concrete grout to 20° - 30°C (67° - 86°F), before using.
Mixing Ratio	
Ratio A:B:C by weight	3:1:54
Ratio A:B:C by volume	3:1:1
Properties at 23°C (73°F) and 50% R.H.	
Density	2300 kg/m ³ (144 lb/ft ³)
Set Life, Min 1" (25.4 mm)	140 min
Compressive Strength ASTM C 671 (MPa psi)	
28 days	23°C (73°F)
3 days	76 (2207)
7 days	76 (2207)
28 days	81 (11762)
	100 (14513)
<small>*Rigid sand and bed of unreinforced concrete</small>	
Tensile Strength ASTM D 638	14.0 MPa (2031 psi)
Elongation ASTM D 638	5.75-1.0%
Flexural Strength ASTM C 595	28 MPa (4061 psi)
Target Modulus of Elasticity in Bending ASTM C 595	19 GPa (2.7 x 10 ⁶ psi)
Coefficient of Thermal Expansion ASTM C 531	
-20°C to 30°C (4°F to 86°F)	2.2 x 10 ⁻⁶ /°C (1.2 x 10 ⁻⁶ /°F)
20°C to 100°C (68°F to 212°F)	3.0 x 10 ⁻⁶ /°C (1.7 x 10 ⁻⁶ /°F)
Bond Strength ASTM C 882	
Joint shear	> 40 MPa (584 psi) concrete failure
Crack Test ASTM C 1181	
4.1 MPa, 60°C (800 psi, 140°F)	4.5 x 10 ⁻¹
2.1 MPa, 80°C (400 psi, 170°F)	3.8 x 10 ⁻¹
Linear Shrinkage ASTM C 531	0.00%
Thermal Compatibility ASTM C 854	No delamination
Exotherm at 22°C (72°F) ASTM D 3671	34.6°C (94.3°F)

- New U-Channel Design Advantages of less grouting (only of Main I-Beams), cheaper construction time, safer design for product leaks or spills path to main drain
- Requires Rigid Base plates (offshore base plates design)
- Experienced a design error as civil wanted the U-channel to reside in the grout layer and mechanical wanted it in the concrete foundation
- Caused some extra time and drawing revision to resolve


PUMPS: DRAINAGE CHANNELS



REVISIONS

NO.	DATE	DESCRIPTION
1		
2		
3		
4		

DESIGNED BY: [Name]
CHECKED BY: [Name]
APPROVED BY: [Name]



- 27 A&V
- 14 RHC
- 8 HMU
- 24 SRC
- 57 U&O

130 PUMP FOUNDATIONS WILL REQUIRE GROUTING EMBEDDED DRAINAGE U CHANNELS

- Need continuous temperature of 25 C, Hoarding required for temperature control even in summer time
- Heat is the key to getting good grout flow
- Important that temp of bags, concrete, foundation & base plate are all constant at temperature prior to starting; may need circulation fans to keep temperature; leave on for 24 hrs post grout (*API 686 Ch 5 par 3.12.9*)
- Perform sample test cubes for quality assurance
- Perform a pre and post level check for verification



25183-110-GQR-C02-00001, Rev. 0
Inspection Test Record (ITR) – Grout Request/Release [C01]

DECEMBER		GROUT REQUEST/RELEASE		C01
CONTRACTOR		SYSTEM NO.		
EQUIPMENT NO.		DRAWING NO.		REV.
TEST DEVICE MFG. S/N		TEST DEVICE TAG NO.		
REFERENCE DOCUMENT NO.		REV.		REMARKS
ITEM TO BE GROUTED	LOCATION	ELEVATION		COMMENTS
REQUESTOR				DATE
LOCATION SKETCH (OPTIONAL)				
PLAN VIEW				
GROUT RELEASE (CHECK IF APPLICABLE) INITIAL AND DATE				
<input type="checkbox"/> CIVIL	<input type="checkbox"/> ELECTRICAL	<input type="checkbox"/> INSTRUMENTATION		<input type="checkbox"/>
<input type="checkbox"/> PIPING	<input type="checkbox"/> MECHANICAL	<input type="checkbox"/> START UP		<input type="checkbox"/>
RELEASED FOR GROUT				DATE
INSPECTION ITEM		ACCEPT	REJECT	NA
REMARKS				
GROUT MATERIAL STORAGE AS PER MANUFACTURERS INSTRUCTIONS		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SURFACES PROPERLY PREPARED		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ITEM TO BE GROUTED IS PROPERLY POSITIONED AND SUPPORTED		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
SHIMS TO BE <input type="checkbox"/> LEFT IN PLACE <input type="checkbox"/> REMOVED		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
GROUT FORMS ADEQUATE		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PRE-SOAK COMPLETE		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
MANUFACTURED GROUT IS AN APPROVED PRODUCT		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
GROUT TYPE:				
GROUT PROPERLY MIXED		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
TEMPERATURES WITHIN SPECIFIED RANGE				
AIR	GRROUTED ITEM			
MIXED GROUT	M&TE ID NO.	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
DRY GROUT	EXPIRATION DATE			
GROUP PLACEMENT METHOD	DATE	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CURING METHOD		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
IF CURING IN COLD WEATHER				
MANUFACTURERS RECOMMENDATIONS FOLLOWED FOR PRE- AND POST- INSTALLATION		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PROPER HEATING AND HOARDING PROVIDED		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CURING COMPLETE, FORMS REMOVED, FINISHING AND/OR PATCHING COMPLETE	DATE	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CLEAN UP COMPLETE		<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
GROUT CUBE TEST RESULTS (COMPRESSIVE STRENGTH)				
3 DAYS	5 DAYS	7 DAYS	28 DAYS	
COMMENTS				
SIGNATURES				
PERFORMED BY	COMPANY	NAME	DATE	
INSPECTOR		PRINT		
		SIGN		
EPCM/SHELL REPRESENTATIVE		PRINT		
		SIGN		
		PRINT		

Field Machining

		Scottford Upgrader Expansion 1		NON-CONFORMANCE REPORT (NCR)		PROJECT # 25183
SECTION 1 – To be completed by Stakeholder						
NCR #:	2	5	1	8	3	-
UNIT NAME		AREA/WBS/WP #:				
CONTRACTOR'S NAME:		CONTRACT #:		STARTUP SYS. #:		
REPORTED BY (print name):		DATE:				
AFFECTED DISCIPLINE:		CODE/ITEM	YES <input type="checkbox"/>	NO <input checked="" type="checkbox"/>		
DRAWING/SPECIFICATION/ITEM #	REVISION #	EQUIPMENT # / DESCRIPTION				
CONTRACT # / P.O. #		CONTRACTOR/SUPPLIER				
NON-CONFORMANCE TYPE	SUPPLIER <input checked="" type="checkbox"/>	CONTRACTOR <input type="checkbox"/>	DAMAGE <input type="checkbox"/>	CONSTRUCTION <input type="checkbox"/>	PROCURE <input type="checkbox"/>	
NON-CONFORMING CONDITION/DESCRIPTION		CHECK IF DIGITAL PHOTO ATTACHED <input type="checkbox"/>				
RECOMMENDED DISPOSITION		REJECT <input type="checkbox"/>	REWORK <input type="checkbox"/>	REPAIR <input type="checkbox"/> [R.E. concurrence required]	USE AS IS <input type="checkbox"/> [R.E. concurrence required]	
DISCIPLINE FIELD ENGR / INSPECTOR'S REVIEW:		Print & Sign			DATE:	
AFE'S CONCURRENCE (print & sign):					DATE:	
FINAL DISPOSITION		REJECT <input type="checkbox"/>	REWORK <input type="checkbox"/>	REPAIR <input type="checkbox"/> [Shell's concurrence required]	USE AS IS <input checked="" type="checkbox"/> [Shell's concurrence required]	
R.E. CONCURRENCE (print & sign)	N.A. <input type="checkbox"/>	DATE	SHELL CONCURRENCE (print & sign)	N.A. <input type="checkbox"/>	DATE	
DESIGN / FIELD CHANGE REQUIRED	YES <input type="checkbox"/>	NO <input type="checkbox"/>	TDN #:	N.A. <input type="checkbox"/>		
DWG/SPEC #:	REV.:	CODE INSPECTOR CONCURRENCE (print & sign)		N.A. <input type="checkbox"/>	DATE	
DCN/FCN/FCR #:	N.A. <input type="checkbox"/>					



- Field Machined 30 out of 251 base plates approximately 12%
- Estimated ~ \$20,000 per base plate and a week to ten days schedule delay to resolve
- Need to be sure if it is the Pump feet or the Pedestal that is to be machined
- Critical for NCR's agreement from vendor prior to grouting


“YOU GROUT IT YOU OWN IT”


Piping Installation

- API 686 Piping Alignment Requirements are defined in **(API 686 Chapter 6 paragraph 4.6.1-4.6.4)**
 - **4.6.1 No Sprung flanges to connect piping (i.e. use of straps, chains, blocking etc.) Experienced no issues with requirement**
 - **4.6.2 Pipe Flange and Pump Flange need to line up within 1/16 inch Experienced no issues with requirement**
 - **4.6.3 Flange Faces shall be parallel to within 0.001 inch per inch of flange outer diameter Experienced no issues with requirement**
 - **4.6.4 Flange face separation shall be within the gasket spacing plus or minus 1/16 inch Experienced many issues with this requirement**

The Issue with 4.6.4:

- The piping designer intentionally allowed a vertical load to be applied to the pump nozzles in the cold condition. (i.e. the piping and pump flanges will be in contact)
- The Piping Fitters were unaware of this intentional load and were trying to meet the dimensions of the isometric drawing and API 686 Ch 6 par 4.6.4
- This caused excessive and costly piping alignment / installation time
- The resolution was to verify the load on the nozzle in the cold condition as per the piping design. This entailed providing the pump nozzle loads to the field and performing verification (i.e. prybar or load weigh scale)
- Adjustment of the spring hangers or spring supports as a method of achieving piping alignment is not acceptable. **(API 686 Chapter 6 paragraph 4.7.3)**. Must be in the cold locked position **Experienced no issues with requirement**





Alignment



25183-110-GQR-MP2-00002, Rev. 0
Inspection Test Record (ITR) – Centrifugal Horizontal Pumps Installation Checklist [M16]

CONTRACTOR		SYSTEM NO.		M16			
EQUIPMENT NO.		DRAWING NO.		REV.			
TEST DEVICE MFG., S/N		TEST DEVICE TAG NO.					
NO.	DESCRIPTION				YES	NA	
VERIFICATION PRIOR TO INSTALLATION							
1	A.2	NAME PLATE DATA IS CORRECT					
2	A.4	SUBMIT INSTALLATION PROCEDURE					
3	A.9	WITNESS POINT (SHELL/EPCM) SIGNATURE					
3	A.9	VERIFY JACKING BOLTS LEVELING PADS DISKS ARE INSTALLED					
4	A.11	VERIFY DRAIN U-CHANNELS UNDER BASEPLATE ARE IN PLACE AND FORMED PER DESIGN					
PRE-INSTALLATION							
5	B.2.2	BOTTOM OF EQUIPMENT SOLEPLATE IS CLEAN, DRY, AND FREE OF CONTAMINANTS					
6	B.2.4	EPOXY PRIMED SURFACES ROUGHENED PRIOR TO EQUIPMENT PLACED ON FOUNDATION					
7	B.2.8	BASEPLATE LEVEL					
7	B.2.8	WITNESS POINT (SHELL/EPCM) SIGNATURE					
8	B.2.9	PRELIMINARY ALIGNMENT					
8	B.2.9	WITNESS POINT (SHELL/EPCM) SIGNATURE					
9	B.2.10	PRELIMINARY SOFT FOOT CHECK					
9	B.2.10	WITNESS POINT (SHELL/EPCM) SIGNATURE					
INSTALLATION							
10	C.2	GROUT POUR/INSPECTION					
11	C.3	SEAL COAT AND GROUT					
12	C.4	TIGHTEN ANCHOR BOLTS					
13	C.5	GROUNDING STRAP					
14	C.6	SOFT FOOT CHECK					
14	C.6	WITNESS POINT (SHELL/EPCM) SIGNATURE					
15	C.7	PIPING/EQUIPMENT/SUCTION SYSTEM CLEANLINESS					
15	C.7	WITNESS POINT (SHELL/EPCM) SIGNATURE					
16	C.8	PIPE STRESS AND FLANGE ALIGNMENT					
16	C.8	WITNESS POINT (SHELL/EPCM) SIGNATURE					
17	C.9	PIPING CLAMPS/SPRING HANGERS INSTALLED AND SET					
18	C.10	VERIFY SUCTION STRAINER IN PLACE					
19	C.11	AUXILIARY PIPING CORRECT LOCATION					
20	C.12	VERIFY VENTS AND DRAINS					
21	C.13	VERIFY SEAL/SEALING SYSTEM INSTALLED					
22	C.14	OIL MIST FITTINGS					
23	C.15	SHAFT TURNS FREELY					
24	C.16	COUPLING: SPACER GAP/AXIAL LENGTH					
24	C.16	OIL SYSTEMS INSTALLED/CHECKED/FLUSHED					
25	C.17	HOLD POINT (SHELL/EPCM) SIGNATURE					
26	C.18	COOLING SYSTEM CHECKED					
27	C.19	FINAL ALIGNMENT IS COMPLETE					
27	C.19	HOLD POINT (SHELL/EPCM) SIGNATURE					
28	C.20	EQUIPMENT HOLDDOWN BOLTS/SHIMS/DOWELS					
29	C.21	SHAFT END FLOAT – WITHIN LIMITS					
30	C.22	GEAR CHECKED (IF APPLICABLE)					
31	C.23	DRIVER CHECKED					
32	C.24	COUPLING ASSEMBLED AND BOLTS TORQUED PER VENDOR REQUIREMENTS. GUARDS INSTALLED.					

25183-110-GQR-MP2-00002, Rev. 0

Page 1 of 2

- Very few alignment issues as all parties agreed that alignment needs to be per API 686
- (API 686 CH 7 par 5.4.2.4) All shims shall be full bearing, with max of 5 shims (API 686 CH 7 par 5.4.2.1)
- We experienced good success with alignment. Success can be attributed to earlier leveling, soft foot checks and rough alignment chart



Key Learning's from Construction


- Job site demands and tasks are ever changing and daily meetings with owner inspection team is vital
- Need a strong relationship between Construction Contractor, Operations and Project Team to ensure clear communication and for rise and resolution of issues
- Our monthly workshops were excellent forums to get alignment and increase trust in building working relationships
- Vendor Representation on site full time to approve NCR's for immediate implementation is vital to construction phase success
- API 686 tolerance of 0.002" per foot is a tight tolerance to achieve
- Ensure all pressure vessels related to rotating equipment (filters, seal pots, etc.) have proper ABSA registration and Canadian registration numbers
- Ensure all tubing related to rotating equipment receives proper documented pressure testing as per requirements stated in Pressure Equipment Safety Regulation Section 4 criteria defined in B31.3 (pressure tubing is to be tested as pressure piping)



Mechanical Completion

- Requires Multidisciplinary Organized Walk downs!
- There will be findings
- Key learning - budget time to resolve issues & determine what needs to be resolved before or after Start-up.

PUNCHLISTING SEASON



Pre-Start-up Issues

- Experienced leaks on pump seals due to poor preservation (residual hydro test fluid)
- Flushing of auxiliary lube oil and barrier fluid systems took a lot of time. Cleanliness issues found
- Motor Bump testing done to IEEE Standard for (TEFC) Totally Enclosed Fan Cooled Squirrel Cage Induction Motors found high vibration issues, resulting in additional stiffening support being required
- The need to loop check and fully function check all instrumentation prior to start up is critical and takes a great deal of effort and time

Rotating Equipment System Walkdown Checklist

1. NCR's complete
2. MOC's complete
3. ITR's complete
4. P&ID matches the field installation
5. Review construction work packages
6. Vendor manual available
7. Instrument tubing supported adequately
8. Ensure all TI's read ambient temperature
9. Instrumentation installed and loop checked
10. Ensure tubing pressure testing is complete
11. Bently Nevada system configured and loop checked
12. Oil Mist system installed
13. Oil mist tubing has correct slope to bearings
14. Oil in bearings
15. Constant level oilers set correctly
16. Breathers installed on bearing housings
17. Seal locking tabs rotated out
18. Ensure plugs in seal glands are correct
19. Ensure tubing connected to mechanical seals
20. Ensure the correct oil is in bearing housings
21. Ensure lube oil system level instrumentation has been calibrated
22. Lube oil flush complete
23. Ensure oil touches the TI in lube oil return lines
24. Insulation and heat tracing installed on lube oil system
25. Aluminium cable trays – check for sharp edges
26. Coupling guards in place
27. Insulation and heat tracing complete
28. Correct gaskets installed

Start-up Issues and Outcome

Issues

- Unanticipated high vibration of pumps running off of BEP
- Minor cavitation issues
- Very few leaks, casing, tubing, instrumentation, etc
- Mechanical Seals preservation damage (residual hydro test fluid)
- Minor vibration of motor bases
- Strainers with a weak delta pressure design

Outcome

- Plant was commissioned and Start-up in Spring of 2011
- No major incidents, and start-up progression achieved a Flawless Start-up

OVERALL SUCCESS!!

Questions

